BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/RD/WORK_INDENT29616

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/23/2017-18, Date:17.02.2018

Package-1, includes 10 works of Rs. 146.50 lakhs

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
1	4	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each	2074.15	Rupees Two Thousand Seventy Four and Fifteen Paise Only
2	200	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.,) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m	Rmtr	337.24	Rupees Three Hundred Thirty Seven and Twenty Four Paise Only
3	200	50 to 100 m	Rmtr	440.84	Rupees Four Hundred Forty and Eighty Four Paise Only
4	200	100 to 150 m	Rmtr	490.43	Rupees Four Hundred Ninety and Forty Three Paise Only
5	200	150 to 200 m	Rmtr	517.99	Rupees Five Hundred Seventeen and Ninety Nine Paise Only
6	200	200 to 250 m	Rmtr	599.54	Rupees Five Hundred Ninety Nine and Fifty Four Paise Only
7	200	250 to 300 m	Rmtr	642.52	Rupees Six Hundred Forty Two and Fifty Two Paise Only

BANGALORE

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
8	380	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1417.75	Rupees One Thousand Four Hundred Seventeen and Seventy Five Paise Only
9	72	Providing 250mm dia PVC Pipe 6kg/cm as per specification and direction of the Engineer in Charge of the work	Rmtr	1177.00	Rupees One Thousand One Hundred Seventy Seven Only
10	6	Providing and fixing 160mm Borewell Cap ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	107.00	Rupees One Hundred Seven Only
11	4	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 10.00 HP 20 stage.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 12.50 HP 20 stage	No	64628.00	Rupees Sixty Four Thousand Six Hundred Twenty Eight Only
12	1040	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	489.97	Rupees Four Hundred Eighty Nine and Ninety Seven Paise Only
13	2160	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	135.57	Rupees One Hundred Thirty Five and Fifty Seven Paise Only
14	176	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) etc., complete and as per the directions of the Engineer-in-charge of the work	m	94.16	Rupees Ninety Four and Sixteen Paise Only
15	6	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	323.14	Rupees Three Hundred Twenty Three and Fourteen Paise Only

Signature of the contractor

16/11

Executive Engineer

16/11

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
16	180	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	150.23	Rupees One Hundred Fifty and Twenty Three Paise Only
17	180	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	11.56	Rupees Eleven and Fifty Six Paise Only
18	150	Digging or trenching of 0.6 m x 0.5 m wide refilling the trench to the required ground level and consolidating etc., complete as per Civil SR KSRB 1-2 P-7 with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	90.95	Rupees Ninety and Ninety Five Paise Only
19	24	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	369.15	Rupees Three Hundred Sixty Nine and Fifteen Paise Only
20	6	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	299.60	Rupees Two Hundred Ninety Nine and Sixty Paise Only
21	6	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia, (PWD Electrical SR-1999-2000, with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	2917.89	Rupees Two Thousand Nine Hundred Seventeen and Eighty Nine Paise Only
22	36	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc.,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	192.60	Rupees One Hundred Ninety Two and Sixty Paise Only
23	4	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	1696.76	Rupees One Thousand Six Hundred Ninety Six and Seventy Six Paise Only
24	4	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	243.85	Rupees Two Hundred Forty Three and Eighty Five Paise Only
25	16	SSupplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour etc., complete and as per the directions of the Engineer-in-charge of the work	No	111.60	Rupees One Hundred Eleven and Sixty Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
26	6	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 30 amps triple pole with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	1655.29	Rupees One Thousand Six Hundred Fifty Five and Twenty Nine Paise Only
27	123000	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.35	and Thirty Five Paise Only
28	4	Supplying fully automatic store detta starter unit push button type with suitable wires three contractors one adjustable termal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3pase and wired offter fixing to the wooden board for motor upto 12.50 HP with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	7043.81	Rupees Seven Thousand Forty Three and Eighty One Paise Only
29	783	Earthwork excavation for pipeline foundation including deporiting or bank up to a depth of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	201.16	Rupees Two Hundred One and Sixteen Paise Only
30	1740	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 75mm Dia 6 KSC	Rmtr	167.99	Rupees One Hundred Sixty Seven and Ninety Nine Paise Only
31	313.2	Sand filling in wells complete as per drawing and technical specifications etc., complete and as per the directions of the Engineer-in-charge of the work	each	3126.99	Rupees Three Thousand One Hundred Twenty Six and Ninety Nine Paise Only
32	469.8	Refilling the bumont and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrswith all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	65.27	Rupees Sixty Five and Twenty Seven Paise Only
33	14	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specification with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each	2920.57	Rupees Two Thousand Nine Hundred Twenty and Fifty Seven Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
34	460.28	Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	213.32	Rupees Two Hundred Thirteen and Thirty Two Paise Only
35	1500	Removing and resetting of footpath slab etc complete as per specifications and directions of engineer in charge of the work	Sqm	141.78	Rupees One Hundred Forty One and Seventy Eight Paise Only
36	91.86	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	6171.18	Rupees Six Thousand One Hundred Seventy One and Eighteen Paise Only
37	623.52	Providing precast slab of 100 mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge	Sqm	1948.00	Rupees One Thousand Nine Hundred Forty Eight Only
38	1522	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	No	355.00	Rupees Three Hundred Fifty Five Only
39	958.5	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	29.49	Rupees Twenty Nine and Forty Nine Paise Only
40	958.5	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	74.86	Rupees Seventy Four and Eighty Six Paise Only
41	3.6	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5723.17	Rupees Five Thousand Seven Hundred Twenty Three and Seventeen Paise Only
42	6.48	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4748.90	Rupees Four Thousand Seven Hundred Forty Eight and Ninety Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
43	4.86	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5676.67	Rupees Five Thousand Six Hundred Seventy Six and Sixty Seven Paise Only
44	21.6	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	111.15	Rupees One Hundred Eleven and Fifteen Paise Only
45	21.6	Providing precast slab of 250 mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge.	Sqm	5483.75	Rupees Five Thousand Four Hundred Eighty Three and Seventy Five Paise Only
46	487.5	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	218.41	Rupees Two Hundred Eighteen and Forty One Paise Only
47	95.4	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	341.00	Rupees Three Hundred Forty One Only
48	15.69	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	5624.31	Rupees Five Thousand Six Hundred Twenty Four and Thirty One Paise Only
49	22.09	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	4838.50	Rupees Four Thousand Eight Hundred Thirty Eight and Fifty Paise Only
50	25.78	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	5783.78	Rupees Five Thousand Seven Hundred Eighty Three and Seventy Eight Paise Only
51	23.6	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	6287.62	Rupees Six Thousand Two Hundred Eighty Seven and Sixty Two Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
52	187.74	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	112.09	Rupees One Hundred Twelve and Nine Paise Only
53	147.24	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	1048.13	Rupees One Thousand Forty Eight and Thirteen Paise Only
54	207.25	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	228.81	Rupees Two Hundred Twenty Eight and Eighty One Paise Only
55	201.4	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	97.07	Rupees Ninety Seven and Seven Paise Only
56	5.7	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members asshown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	3390.53	Rupees Three Thousand Three Hundred Ninety and Fifty Three Paise Only
57	42.75	Sand Filling in Foundation Trenches as per Drawing & Technical etc complete as per specifications and directions of engineer in charge of the work	Cum	3126.99	Rupees Three Thousand One Hundred Twenty Six and Ninety Nine Paise Only
58	90	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	29.49	Rupees Twenty Nine and Forty Nine Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
59	1	Providing Children play Merry-go-Round equipment : Made of MS 'A' Class pipes. Main pillars in 100 mm dia fitted with shaft and two bearing the other cross members are in 25 & 20 mm MS A Class pipe the bottom ring is made out of 25mm of ring size is 1.20 mts dia fitted with four seats are in mental sats if 250 x 200 x 18 SWG handles are made out of 20mm NB pipes and othe supports are in 25mm MS 'A' Class pipes. All the pipes are painted with two coats of super set paint over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	29960.00	Rupees Twenty Nine Thousand Nine Hundred Sixty Only
60	1	Providing Children Play Standard Swing : This Swing consosts of 2 Nos, seat of solid fibbed FP of size 480 mm x 180 mm x 3.5 mm supported by MS chains. The chains are supported by circular housing with bearing from which the chain in suspended. The main beam is of 50 mm MS 'A' class pipe Size of MS chain 30 mm x 20 mm x 5mm thick The 2 Nos inverted 'V' beams are of 50 mm 'A' class pipes secured at the top the main beam by means of CI castings (Heavy duty for elders) All pipes are of ISI grade all the pipes are painted with two coats of super set paitng over a coat of protective Zinc chromate yellow oxide including fixing the play equipments in CC 1:2:4, curing etc., complete with all lead, lift, loading, unloading and any other incidental charges and as perthe draing and specification and direction of the engineer in charge of the work.	Each	59920.00	Rupees Fifty Nine Thousand Nine Hundred Twenty Only
61	1	Duck wheel etc complete as per specifications and directions of engineer in charge of the work	Each	72760.00	Rupees Seventy Two Thousand Seven Hundred Sixty Only
62	1	Duck Swing (2 seater) etc complete as per specifications and directions of engineer in charge of the work	Each	59920.00	Rupees Fifty Nine Thousand Nine Hundred Twenty Only
63	1	Mini Slide etc complete as per specifications and directions of engineer in charge of the work	Each	17120.00	Rupees Seventeen Thousand One Hundred Twenty Only
64	6	Providing Granite Benches etc complete as per specifications and directions of engineer in charge of the work	Each	10700.00	Rupees Ten Thousand Seven Hundred Only
65	4.52	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	223.03	Rupees Two Hundred Twenty Three and Three Paise Only
66	204.26	Providing 20mm thick cement plaster in single coat with cement mortar 1:6, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	240.36	Rupees Two Hundred Forty and Thirty Six Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
67	8.33	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	28.89	Rupees Twenty Eight and Eighty Nine Paise Only
68	50.01	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	82.05	Rupees Eighty Two and Five Paise Only
69	176.17	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	97.07	Rupees Ninety Seven and Seven Paise Only
70	4.56	Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 30x30cms 6mm thick etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	1358.99	Rupees One Thousand Three Hundred Fifty Eight and Ninety Nine Paise Only
71	4.8	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. size of gate 2.4mx1.4m. etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	4660.53	Rupees Four Thousand Six Hundred Sixty and Fifty Three Paise Only
72	65.4	Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 - Colour glazed tiles 15x15 cms 6mm thick etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	1238.80	Rupees One Thousand Two Hundred Thirty Eight and Eighty Paise Only
73	24.57	SOLID PVC DOOR FRAME Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	607.85	Rupees Six Hundred Seven and Eighty Five Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
74	3.15	SOLID PANEL PVC DOOR SHUTTER Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19x19mm fro styles and 15x15mm for top & bottom rails, covered with heat moulded PVC channel of 5mm thick sheet & 30 x 50mm wide to form styles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the styles & rails with 5x30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 m.m Aluminium hinges etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	3689.83	Rupees Three Thousand Six Hundred Eighty Nine and Eighty Three Paise Only
75	200	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 20mm nominal OD pipes etc., complete and as per the directions of the Engineer-in-charge of the work	M	242.68	Rupees Two Hundred Forty Two and Sixty Eight Paise Only
76	195	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spat & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25mm nominal OD pipes etc., complete and as per the directions of the Engineer-in-charge of the work	m	288.90	Rupees Two Hundred Eighty Eight and Ninety Paise Only
77	10	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads etc., complete and as per the directions of the Engineer-in-charge of the work	Each	693.36	Rupees Six Hundred Ninety Three and Thirty Six Paise Only
78	40	Providing and fixing to wall, ceiling and floor, low density polyethylene pipes 6.00 kgf/sq.cm working pressure 140mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing etc., complete and as per the directions of the Engineer-in-charge of the work	m	614.78	Rupees Six Hundred Fourteen and Seventy Eight Paise Only
79	4	Constructing brick masonry inspection chamber 455 x 610 mm and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	8136.58	Rupees Eight Thousand One Hundred Thirty Six and Fifty Eight Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
80	2	Providing and fixing white vitreous china clay, surgeon type wash basin size 660x460mm with a pair of 15mm C.P brass pillar taps with pair of elbow operated levers, C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour etc., complete and as per the directions of the Engineer-in-charge of the work	Unit	5291.49	Rupees Five Thousand Two Hundred Ninety One and Forty Nine Paise Only
81	10	Providing and fixing in position brass bib cock of approved quality 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads etc., complete and as per the directions of the Engineer-in-charge of the work	Each	317.79	Rupees Three Hundred Seventeen and Seventy Nine Paise Only
82	2	Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580 x 440mm with integral type footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour etc., complete and as per the directions of the Engineer-in-charge of the work	Pan	5010.68	Rupees Five Thousand Ten and Sixty Eight Paise Only
83	1	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity) etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	9784.47	Rupees Nine Thousand Seven Hundred Eighty Four and Forty Seven Paise Only
84	8	Providing and fixing 453x357mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour etc., complete and as per the directions of the Engineer-in-charge of the work	Unit	1363.61	Rupees One Thousand Three Hundred Sixty Three and Sixty One Paise Only
85	1	Outdoor PLZ IP Cameras with 20 X optical zoom with controller along with suitable mounting system (PTZ Pan Tilt and Zoom feature is availbale in this camera can be contolled by the software for pan Tilt and zoom feature at the contol center and can be programmed to view at different angles and zoom level continuosly. It operates at day and night and the viewing distance at clarity is about 100 metres	Nos	83954.34	Rupees Eighty Three Thousand Nine Hundred Fifty Four and Thirty Four Paise Only
86	6	Bracket (Corner Mount / Pole Mount/ Wall Mount) for mounting the PTZ camera.	Nos	4565.69	Rupees Four Thousand Five Hundred Sixty Five and Sixty Nine Paise Only
87	6	Outdoor 50 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 50 metres)	Nos	22641.20	Rupees Twenty Two Thousand Six Hundred Forty One and Twenty Paise Only
88	6	Bracket and weatherproof Installation kit for 50 Meter IP Camera	Nos	1653.15	Rupees One Thousand Six Hundred Fifty Three and Fifteen Paise Only
89	6	Outdoor 30 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 30 metres)	Nos	16328.20	Rupees Sixteen Thousand Three Hundred Twenty Eight and Twenty Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
90	6	Bracket and weatherproof Installation kit for 30 Meter IP Camera	Nos	1595.37	Rupees One Thousand Five Hundred Ninety Five and Thirty Seven Paise Only
91	1	32 Channel NVR DS 7732 NI- E4 (with 4 Sata Option) the control box and the recording device to connect upto 32 devices, can be cascaded to provide additional cameras	Nos	71670.74	Rupees Seventy One Thousand Six Hundred Seventy and Seventy Four Paise Only
92	1	12 TB NAS Box for Back up (NET GEAR) provides storage for the recorded data for quick view back and storage	Nos	275439.40	Rupees Two Hundred Seventy Five Thousand Four Hundred Thirty Nine and Forty Paise Only
93	2	4 TB SATA for storage and fitted in the NVR Device for storage	Nos	24449.50	Rupees Twenty Four Thousand Four Hundred Forty Nine and Fifty Paise Only
94	12	A suitable sheet metal control panel to house site Equipments (Weather Proof) The power supply and the ethernet connectivity adaptor is stored in this box.	Nos	1632.82	Rupees One Thousand Six Hundred Thirty Two and Eighty Two Paise Only
95	12	Power supply for the camera.	Nos	493.27	Rupees Four Hundred Ninety Three and Twenty Seven Paise Only
96	12	Ethernet Switch for connectivity to Internet and Camera	Nos	1016.50	Rupees One Thousand Sixteen and Fifty Paise Only
97	9	Supply & Laying of Network and Power Cables from Camera to the control Box.	Nos	416.23	Rupees Four Hundred Sixteen and Twenty Three Paise Only
98	6	Video Manager Application Software for Display and Management of Camera on Video Display.	Nos	21400.00	Rupees Twenty One Thousand Four Hundred Only
99	6	Installation, Erection & commissioning charges	Nos	5414.20	Rupees Five Thousand Four Hundred Fourteen and Twenty Paise Only
100	2.32	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms)(item no 37.51page no 258)	Cum	170.56	Rupees One Hundred Seventy and Fifty Six Paise Only
101	11.62	KSRRB M200-14.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. ii) Dismantling brick/Tile work B. In cement mortar. MORTH Specification No. 202	Cum	388.97	Rupees Three Hundred Eighty Eight and Ninety Seven Paise Only
102	20.38	KSRB 2.14-1: Extra for additional lift of 1.5m. or part thereof for excavation In loose / soft or hard soil including cost of materials, labour complete as per specifications. (Page no -7, item no - 2.21)	Cum	233.43	Rupees Two Hundred Thirty Three and Forty Three Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
103	18.46	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 465 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth, including cost of all material, labour HOM Machinery curing complete as per specification,(Page. No. 12 Item No. 4.2	Cum	5831.16	Rupees Five Thousand Eight Hundred Thirty One and Sixteen Paise Only
104	44.09	KSRB 5.1-3 : Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6 (uncoursed), bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.12(Page. No. 22 Item No.5.3)	Cum	3754.54	Rupees Three Thousand Seven Hundred Fifty Four and Fifty Four Paise Only
105	31.2	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2(Page No : 15, item No : 4.28)	Sqm	266.94	Rupees Two Hundred Sixty Six and Ninety Four Paise Only
106	74.36	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No : 16, item No : 4.32)	Sqm	422.95	Rupees Four Hundred Twenty Two and Ninety Five Paise Only
107	55.24	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page No : 16, item No : 4.31)	Sqm	338.59	Rupees Three Hundred Thirty Eight and Fifty Nine Paise Only
108	98.85	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitonsupto 3.50m from ground level. Specification No. KBS 4.6.2(Page No : 15, item No : 4.18)	Sqm	361.70	Rupees Three Hundred Sixty One and Seventy Paise Only
109	65.18	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page No : 16, item No : 4.34)	Sqm	295.83	Rupees Two Hundred Ninety Five and Eighty Three Paise Only
110	17.95	KSRB 4.2.8: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles, and beams retaining walls, return walls, walls (any thickness) including attached plasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6. (P. No. 14/ I.No. 4.13	Cum	7116.18	Rupees Seven Thousand One Hundred Sixteen and Eighteen Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
111	7.66	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500 (Page No : 17, item No : 4.46.2)	Tonne	70037.45	Rupees Seventy Thousand Thirty Seven and Forty Five Paise Only
112	22.93	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto SO m. and lift upto 1.S m. including cost of all labour complete as per specifications. specification. No. KBS(Page No : 6, item No : 2.10)	Cum	146.76	Rupees One Hundred Forty Six and Seventy Six Paise Only
113	136.12	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4(Page No :25, item No : 5.27.1)	Sqm	1082.80	Rupees One Thousand Eighty Two and Eighty Paise Only
114	156.11	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4(Page No :25, item No : 5.27.2)	Sqm	1048.13	Rupees One Thousand Forty Eight and Thirteen Paise Only
115	468.16	KSRB15-3.4 : Providing 15mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications...(Page No.113, Item No.15.12)	Sqm	236.90	Rupees Two Hundred Thirty Six and Ninety Paise Only
116	98.85	KSRB15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.No. 113, I.No. 15.21 of PWD SR 2015-16)	Sqm	223.03	Rupees Two Hundred Twenty Three and Three Paise Only
117	468.16	KSRB 15.10.2 Providing white washing for every one additional coat with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications. (Page No. 115, Item No. 15.39)	Sqm	4.62	Rupees Four and Sixty Two Paise Only
118	98.85	KSRB 15.10.4 Providing white washing to ceiling and / or sloping roof surface with additional one coat with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications.(Page No. 115, Item No. 15.41)	Sqm	4.62	Rupees Four and Sixty Two Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
119	200.45	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer. (P. No. 118, I.No. 15.53.2).	Sqm	100.54	Rupees One Hundred and Fifty Four Paise Only
120	235.58	Providing and applying two coats with Plastic emulsion paint of approved brand wall surface to a give an even approved shade after throuughly brushing the surface,free from mortar drops and other foreign matter, including priming , including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications,with primer. (Page No : 117, item No :15.51.2)For internal walls.	Sqm	104.00	Rupees One Hundred Four Only
121	98.85	Providing and applying two coats with Plastic emulsion paint of approved brand wall surface to a give an even approved shade after throuughly brushing the surface,free from mortar drops and other foreign matter, including priming , including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications,with primer. (Page No : 117, item No :15.51. 2 & 3) for ceiling	Sqm	108.63	Rupees One Hundred Eight and Sixty Three Paise Only
122	106.9	KSRB 14.14-5: Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles 400 x 400mm on a bed of 20mm thick (Page No : 106, item No :14.36.3)	Sqm	1361.30	Rupees One Thousand Three Hundred Sixty One and Thirty Paise Only
123	232.58	KSRB 14.14-5: Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. - for Ceramic Tiles of size 30x30cms 6mm thick. (P.No.106, I.No. 14.36.2)	Sqm	1358.99	Rupees One Thousand Three Hundred Fifty Eight and Ninety Nine Paise Only
124	9.72	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 1200mm (P.No.107, I.No.14.47.1)	Sqm	3026.52	Rupees Three Thousand Twenty Six and Fifty Two Paise Only
125	319.41	KSRB 7.9:Providing and fixing M.S.gill work for windows and ventilators using M.S.flats, or M.S. square rods, or combination of M.S.flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12 . (Page No : 32, item No :7.9)	Kgs	90.14	Rupees Ninety and Fourteen Paise Only
126	0.16	KSRB 9.4-2 : Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33	Cum	118859.24	Rupees One Hundred Eighteen Thousand Eight Hundred Fifty Nine and Twenty Four Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
127	4.2	KSRB 9.5-2 : Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34	Sqm	5365.45	Rupees Five Thousand Three Hundred Sixty Five and Forty Five Paise Only
128	13.56	KSRB 7.10 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. with 1.2mm thick, bottom section weight 0.695 kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg./m; shutter outer side 40mmx18mm, 1.25mm.thick weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; and providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted in the assembled frame stiffened with end clips at corners angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium sections pretreated for removal of any Specification No. KBS using aluminium section anodized to 12 - 15 microns. (P.No. 301/ I. No. 7.10.1	Sqm	4412.08	Rupees Four Thousand Four Hundred Twelve and Eight Paise Only
129	4	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks as per IS 12701 : 1996 with manhole lid and suitable locl<ing arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications.(For 1 000 litre capacity) Specification No.KBS 13.22 (P.No.94, I.No.13.78 of PW, P&IWTD S.R 2016-17)	Each	9784.47	Rupees Nine Thousand Seven Hundred Eighty Four and Forty Seven Paise Only
130	70	KSRB13-8.5 : Providing and fixing to wall, ceiling and floor, low density polyethylene pipes 6.00 kgf/sq.cm working pressure 110mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9(P.No.94, I.No.13.70.4 of PW, P&IWTD S.R 2016-17)	Mtr	411.39	Rupees Four Hundred Eleven and Thirty Nine Paise Only
131	40	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. (P.No. 88, I.No. 12.111 of PWD SR 2016-17)	Each	184.90	Rupees One Hundred Eighty Four and Ninety Paise Only
132	40	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms (P.No. 88, I.No. 12.113.1 of PWD SR 2016-17)	Each	288.90	Rupees Two Hundred Eighty Eight and Ninety Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
133	25	KSRB13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3 (P.No. 91, I.No. 13.23 of PWD SR 2016-17)	Each	280.81	Rupees Two Hundred Eighty and Eighty One Paise Only
134	20	KSRB13-6.3-3 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. (P.No.91/ I.No. 13.34 of CSR 2016-17)	Each	693.36	Rupees Six Hundred Ninety Three and Thirty Six Paise Only
135	25	KSRB13-6.3-3 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. (P.No.91/ I.No. 13.33 of CSR 2016-17)	Each	472.64	Rupees Four Hundred Seventy Two and Sixty Four Paise Only
136	8	Constructing brick masonry inspection chamber 450x450mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 450x450mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 450x450mm (P.No. 73/ I.No.11.50.2 of PWD SR 2016-17)	Nos	6175.53	Rupees Six Thousand One Hundred Seventy Five and Fifty Three Paise Only
137	6	KSRB 11-2 : Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580 x 440mm with integral type footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11. (P.No. 77, I.No.12.2 of PWD SR 2015-16).(P.No.77 I.No.12.2 of CSR 2016-17)	Each	5010.68	Rupees Five Thousand Ten and Sixty Eight Paise Only
138	19	KSRB 11-5 : Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11. (P.No. 77, I.No.12.5 of PWD SR 2015-16).(P.No.77 I.No.12.2 of CSR 2016-17)	Each	5928.23	Rupees Five Thousand Nine Hundred Twenty Eight and Twenty Three Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
139	9	KSRB 11-7.4 : Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm in the range of four with 10 litres PVC automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11. (P.No. 77, I.No.12.2 of PWD SR 2015-16).(P.No.77 I.No.12.10 of CSR 2016-17)	Each	7869.64	Rupees Seven Thousand Eight Hundred Sixty Nine and Sixty Four Paise Only
140	9	KSRB 11-11.1 : Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (P.No.80 I.No.12.23 of CSR 2016-17)	Each	4490.66	Rupees Four Thousand Four Hundred Ninety and Sixty Six Paise Only
141	52.28	Fabricating, supplying and erecting M.S. TubularTruss of span upto 10m. The bottom and top member is provided with 50x50x6mm double equal angles, welded back to back and in between top and bottom line, in areas of mid section is provided with 50x50x6mm equal single angle for vertical and inclined members and at supporting ends 40x40x5mm single angle is provided. All the members are welded together with 6mm gusset plate as per Drawing. The entire truss is anchored in RCC column by using 4 Nos. of M.S. anchor bolts at each support, with 10mm thick base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S angle and wleding wherever necessary, and applying one coat of red oxide primer coat to all themembers including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, etc., complete as per specification. (Page No. 40 Item No. 7.29 of CSR 2015-16)	Each	127.12	Rupees One Hundred Twenty Seven and Twelve Paise Only
142	20.64	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses.	Each	889.81	Rupees Eight Hundred Eighty Nine and Eighty One Paise Only

KBR INFRATECH PVT. LTD. BANGALORE

Signature of the contractor

16/11

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
143	2	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.48, I. 9.4) PRED.SR 2012-13	ach BV	2013.74	Rupees Two Thousand Thirteen and Seventy Four Paise Only
144	100	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13 (0 to 50 Mtr)	Rmtr	327.42	Rupees Three Hundred Twenty Seven and Forty Two Paise Only
145	100	50 to 100 m	Rmtr	428.00	Rupees Four Hundred Twenty Eight Only
146	100	100 to 150 m	Rmtr	476.15	Rupees Four Hundred Seventy Six and Fifteen Paise Only
147	100	150 to 200 m	Rmtr	502.90	Rupees Five Hundred Two and Ninety Paise Only
148	120	200 to 260 m	Rmtr	582.08	Rupees Five Hundred Eighty Two and Eight Paise Only
149	36	Providing 250mm dia PVC Pipe 6kg/cm SE PRED Approved Rate	Rmtr	807.28	Rupees Eight Hundred Seven and Twenty Eight Paise Only
150	2	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps PWD SR 2016-17 P. XXXXII Item No. 24 including of all taxes	No	79501.00	Rupees Seventy Nine Thousand Five Hundred One Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
151	500	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark No 3/08-09 2406/15.10.2008	Rmtr	401.25	Rupees Four Hundred One and Twenty Five Paise Only
152	88	Heavy Duty Collar 50 mm dia	Nos	139.10	Rupees One Hundred Thirty Nine and Ten Paise Only
153	510	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A. P. No. 12 / I No. 2.10.4(1) 3C x 6 Sqm mm KPWD Electrical SR 2014-15	Mtr	201.91	Rupees Two Hundred One and Ninety One Paise Only
154	2	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involoved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) (As per rate approved KUWS & DB for year 2008-09	Nos	3210.00	Rupees Three Thousand Two Hundred Ten Only
155	2	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 Page No. 93 Item No. 13.55 / PWD SR 2016-17	Nos	1728.78	Rupees One Thousand Seven Hundred Twenty Eight and Seventy Eight Paise Only
156	2	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. P. No. 95 / I. No. 13.81.3 PWD SR 2016-7	Nos	248.45	Rupees Two Hundred Forty Eight and Forty Five Paise Only
157	8	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc complete	Nos	85.60	Rupees Eighty Five and Sixty Paise Only
158	2	Supplying shunt capaitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift =, loading, unloading and labour charges etc complete as per specifications	Nos	374.50	Rupees Three Hundred Seventy Four and Fifty Paise Only

KBR INFRATECH PVT LIMITED BANGALORE

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
159	2	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. 12.5HP to 15 HP Star Delta Starter SERDED Rate	Nos	11770.00	Rupees Eleven Thousand Seven Hundred Seventy Only
160	54	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil	Cum	201.16	Rupees Two Hundred One and Sixteen Paise Only
161	120	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 item No.3.4.2 b PRED SR 2012-13.	Rmtr	167.99	Rupees One Hundred Sixty Seven and Ninety Nine Paise Only
162	54	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13	Cum	65.27	Rupees Sixty Five and Twenty Seven Paise Only
163	2	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 92 / I.13.37 PWD SR - 2016-17	Each	2371.29	Rupees Two Thousand Three Hundred Seventy One and Twenty Nine Paise Only
164	19.5	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 (Page No : 13, item No : 4.11)	Cum	6946.31	Rupees Six Thousand Nine Hundred Forty Six and Thirty One Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K BABU RAJU	
				In Figures	In Words
165	23.22	SOLID PANEL PRELAM PVC DOOR SHUTTER Providing & fixing 30mm thick factory made rigid foam Prelam Panelled Door Shutters made from M.S. tube of 19x19mm, 19 gauge for styles and 15x15mm for top & bottom rails, covered with heat moulded Prelaminated PVC C Channel of 5mm thick sheet & 30x50mm wide to form styles & 5mm thick & 75mm wide Prelaminated PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, Sealed to the styles & rails with PVC Designer beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75mm. Aluminium hinges. with both side prelam(item no 9.85.1 page no 58)	Sqm	4674.40	Rupees Four Thousand Six Hundred Seventy Four and Forty Paise Only
166	10	Providing Modern Dust Bins	Nos	14445.00	Rupees Fourteen Thousand Four Hundred Forty Five Only

KBR INFRATECH (I) PVT. LTD. BANGALORE

Signature of the Contractor

16/11

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/11